



Ref. No. USIC/2020-21/

Date: 06-08-2020

INVITATION FOR QUOTATION

Sir

The university invites sealed quotations for supply and installation of following material using your own tools/instruments and manpower. Please verify yourself the actual place of installation and quantity of material required. The details are as given below.

Sr. No.	Material/Work	Qty.	Make	Type	Per Unit Rate/ per meter rate	Total Amount Rate
1	Supply of 100 Pair jelly filled unarmored U/G Telephone cable 0.5 mm dia. copier conductor	100 Meter				
2	Supply of 50 Pair jelly filled unarmored U/G Telephone cable 0.5 mm dia. copier conductor	150 Meter				
3	Supply of Jointing Kit for 100 pair telephone cable.	06 Nos.				
4	Supply of Jointing Kit for 50 pair telephone cable.	10 Nos.				
5	Supply of Jointing Kit for 10 pair telephone cable.	10 Nos.				
6	water proof D.P. 200 pair with crone	02 Nos.				
7	water proof D.P. 100 pair with crone	01 Nos.				
8	water proof D.P. 50 pair with crone	01 Nos.				
9	water proof D.P. 20 pair with crone	05 Nos.				
10	Roget Box	200 Nos.				
11	1 inch patti/casing & capping With Installation	100 Nos.				
12	1 pair cable 500/M Drop wire Outdoor one pair 0.5mm diameter copper conductors cable with reinforcing thread.	02 Nos.				
13	2 pair cable 90/M bundle	05 Nos.				
14	Telephone Instrument • 3-Step Ringer volume control (LO/ME/HI) • Desktop and wall mountable • Pulse/Tone dialing mode switchable	43 Nos.				
15	Route maker	10 Nos.				
Labor work						
16	(wxbxd) 1 Feet X 2 Feet x 1 M) deep trenching in tar-road-side soil, cable lying, refilling & compacting complete.	250 Meter				

17	Connecting 50 pairs of the supplied cable to the existing Krone modules of the Junction Box and testing connections. 50 Pair jelly filled U/G Unarmored Telephone cable, 0.5 mm dia. copier conductor. 0.5 meter deep trenching in tar-road-side soil,	30 Nos.				
18	100pair cable Jointing & Jointing kit installation	10 Nos.				
19	50 pair cable Jointing & Jointing kit installation	06 Nos.				
20	10 pair cable Jointing & Jointing kit installation	10 Nos.				
21	Cable Tracking Charges (Cable Fault Finding)	07 Job.				

If you are interested, please quote your rate in above format inclusive of all taxes and any other charges and considering terms & conditions given herein below.

Terms & Conditions.


1. Warranty should be provided for any defects in the carried out work. The period of warranty should be clearly expressed in your quotation & scope of warranty should include all the material and services required to set right the defects in the carried out work if reported to you during the warranty period.
2. The work should be carried out at Dr. Babasaheb Ambedkar Marathwada University, Aurangabad.
3. The supplier should take care not to damage any electrical, telecommunication cables and water pipes while carrying out the work. The supplier should be responsible to set-right any such damage at his own cost if occurs during installation work.
4. Payment shall be made by cheque after complete execution of the ordered work & its acceptance by the University for Correctness in quality & quantity.

Please send your quotation to, Head, USIC, Dr. Babasaheb Ambedkar Marathwada University Aurangabad on or before 14-08-2020 up to 04:00 pm in sealed envelope super scribed as =>

“Quotation for 100 & 50 pair Cable due on 14-08-2020”.

Please enclose following mandatory documents along with the sealed quotation envelope.

1. Copy/Receipt of updated Registration of Business or Shop Act License.
2. Copy of PAN card.
3. GST registration.



Head

University Science Instrumentation Center (USIC),
Dr. Babasaheb Ambedkar
Marathwada University, Aurangabad

Copy to: Director, U.N.I.C. for publishing this Quotation Invitation on university's website.